



Construction glue the floor joists. Don't forget to fill the cavity with loose-fill cellulose insulation first. Nails: 12d

2 Sheets 4x8 OSB T&G Flooring, cut to 6ft length \$36 each, Santee HD, 23/32"  
 7 pieces 2x6x69in, cut from 4x 12ft 2x6's, 2 in. x 6 in. x 12 ft. #2 and Better Prime Douglas Fir Lumber \$12.72 @ El Cajon or Santee HD  
 2 pieces 2x6x8' \$8.48

Penny size	Length (inches)	Length (nearest mm)
2d	1	25
3d	1¼	32
4d	1½	38
5d	1¾	44
6d	2	51
7d	2¼	57
8d	2½	64
9d	2¾	70
10d	3	76
12d	3¼	83
16d	3½	89
20d	4	102
30d	4½	114
40d	5	127
50d	5½	140
60d	6	152